BRUHATH BANGALORE MAHANAGARA PALIKE

Yelahanka Division

Work Slip: As per Std Tender Documents

Name of Work: **Asphalting to roads at Ambhabhavani layout and surrounding area in ward no: 03 Yelahanka satellite Town Sub division**

Estimate Amount:- **2,00,00,000/-**

Name of Contractor:- **M/s KRIDL**

Approved amount:- **16,939,682.00**

Tender premium:- **--**

Sl. No.	Description of Work	Unit	Qty as per Quoted Rate			Total Qty Executed	Qty. as per Anticipated upto 125%			Qty. as per Anticipated above 125%			Total Amount	excess amount	Savings amount	Remarks
			Qty	Rates	Amount		Qty.	Rates	Amount	Qty.	Rates	Amount				
1	2	3	4	5	6	10	11	12	13	14	15	16	17	18	19	20
1	KSRRB300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	962.42	211.79	203831.44	1340.48	1203.03	211.79	254789.30	137.46	211.79	29111.59	283900.89	80069.45	0.00	
2	KSRRB M2900-1. Plain cement concrete M10 mix with crushed stone aggregate 40mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing including cost of materials, labour, HOM complete as per the specification	Cum	143.99	4479.56	645011.84	196.90	179.99	4479.56	806264.81	16.91	4479.56	75760.56	882025.37	237013.53	0.00	
3	KSRRB M2200-6. Providing TMT Bars Fe 500 steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in postion, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification.	Ton	18.50	72326.98	1338049.13	24.34	23.13	72326.98	1672561.41	1.22	72326.98	88095.71	1760657.12	422607.99	0.00	
4	Providing and laying plain/reinforced cement concrete for side drains wall & bottom thickness 15cm using M20 nominal mix concrete with OPC at 300 kgs with 29mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregate at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specifications.	Cum	295.13	7070.20	2086610.45	395.28	368.91	7070.20	2608263.06	26.37	7070.20	186410.24	2794673.30	655670.21	0.00	

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Bruhat Bengaluru Mahanagara Palike

cription of Work	Unit	Qty as per Quoted Rate			Total Qty Executed	Qty. as per Anticipated upto 125%			Qty. as per Anticipated above 125%			Total Amount	excess amount	Savings amount	
		Qty	Rates	Amount		Qty.	Rates	Amount	Qty.	Rates	Amount				
2	3	4	5	6	10	11	12	13	14	15	16	17	18	19	
upplying and fixing precast reinforced concrete slab 0cm thick of mix M20 using 20mm and downsize graded granite metal using reinforcement 10mm dia steel at 150mm C/c both ways cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges , labour charges inclusive of cost of cost of all materials (data Rate enclosed)	Sqm	603.45	2337.00	1410262.65	888.75	754.31	2337.00	1762828.31	134.44	2337.00	314180.44	2077008.75	666746.10	0.00	
7 Providing and fixing pre cast solid concrete kerb stones of size 450x200x400 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete.	Nos	687.00	477.00	327699.00	1378.00	858.75	477.00	409623.75	519.25	477.00	247682.25	657306.00	329607.00	0.00	
8 KSRRB 800-1 Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	93.60	84.80	7886.40	186.09	116.25	84.80	9858.00	69.84	84.80	5922.43	15780.43	7894.03	0.00	
Grand total								7524188.64			947163.22	8471351.86	2399608.31	0.00	

Note: Percentage of Workslip over the sanctioned Estimate=Excess amount over the approved amount/ Approved Amount x 100

Approved Amount =	16939682.00
Excess Amount =	2399608.31
Savings Amount =	0.00

$$\text{Percentage of Worslip} = \frac{\text{Excess Amount}}{\text{Approved Amount}} \times 100$$

Percentage of Worslip =	14.17 %

Assistant Engineer

"WORKSLIP APPROVED"
ಮುಖ್ಯ ಕಾರ್ಯಪಾಲಕ ಅಧಿಕಾರಿಗಳು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ಉಪನಗರ ಉಪವಿಭಾಗ,
ಬಿ.ಬಿ.ಎಂ.ಪಿ. ಬೆಂಗಳೂರು-106
Assistant Executive Engineer

Executive Engineer
B.B.M.P Division
Yelahanka

BRUHAT BANGALORE MAHANAGARA PALIKE

Yelahanka Division

Name of work:- Asphalting to roads at Ambhabhavani layout and surrounding area in ward no: 03 Yelahanka satellite Town Sub division

EIRL

Estimate Amount:- Rs 2,00,00,000/-
Approved Amount:- Rs 16939682/-
Name of Contractor:- M/s KRIDL
Tender premium:- ---

Sl. No.	Description of Work	Unit	Quantity	Rate	Amount in Rupees	Whether item alternate to item in the tender or whether they are additional item (if, in lieu of the same item in the accepted tender such items should be mentioned.	Whether the extra item is included in the sanctioned estimate.	How the extra cost of the item is proposed to be met	Whether the extra item is included in the Schedule of rates of the division, if not, data sheet should accompany the rate list.	Remarks
1	2	3	4	5	6	7	8	9	10	11
E1	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/trap/basalt material, mixing by mix in place method by rotavator at OMC,spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per	Cum	778.01	1994.92	1552066.71	ADDITIONAL ITEM	No		P.No-27,I No-5.30, KPWD SR 2018-19	
E2	KSRRB M800-35. Supply and Installtion of Moulded Shank Raised Pavement Markers made of polycarbonate and ABS(Acrylonitrile Butadiene Styrene) moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering the lens face and shall support a load of 16000 kg tested in accordance to Specifications of Category A of MORTH Circular No RW/ NH/33023/10-97 – DO III Dt 11.06. 1997. The height, width and length shall not exceed 50 mm, 100 mm and 102 mm and with minimum reflective area of 13 Sqcm on each side and the slope to the base shall be 35 degree. The strength of detachment of the integrated cylindrical shanks, (of diameter not less than 19 mm and height not less than 30 mm) from the body is to be a minimum value of 500 Kg. Fixing will be by drilling holes on the road for the shanks to go inside, without nails and using epoxy resin based adhesive as per manufacturer's recommendation and complete as directed by	Nos	248.00	357.22	88590.56	ADDITIONAL ITEM	No		P.No-180,I No-24.1, KPWD SR 2018-19	
				TOTAL ERIL AMOUNT	1640657.27					

Note: Percentage of Extra item over the sanctioned Estimate=Extra item amount over the approved amount/Amount Put to tender x 100

Total cost as per Approved Amount, Rs =	16939682.00
Total cost of EIRL Amount, Rs=	1640657.27
Percentage of Worslip = EIRL Amount / Approved Amount X 100	
% of EIRL =	9.69

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Assistant Engineer

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರ
ಯಲಹಂಕ ಉಪನಗರ ಉಪವಿಭಾಗ.
ಬ ಬ.ಎಂ.ಪ. ಬೆಂಗಳೂರು-106

Executive Engineer
B.B.M.P Division
Yelahanka

Yelahanka
Bruhat Bengaluru Mahanagara Palike

BRUHATH BANGALORE MAHANAGARA PALIKE

Yelahanka Division

Comparitive Statement

Name of Work: Asphalting to roads at Ambhabhavani layout and surrounding area in ward no: 03 Yelahanka satellite Town Sub division

Estimate Amount:- 2,00,00,000/-

Name of Contractor:- M/s KRIDL

Approved amount:- 16,939,682.00

Tender premium:- ---

Sl. No.	Description of Work	Unit	Qty as per ScheduleB			Total Qty Executed	Qty. as per Actuals upto 125%			Qty. as per Actuals above 125%			Total		Difference		Remarks
			Qty	Rates	Amount		Qty.	Rates	Amount	Qty.	Rates	Amount	Qty	Amount	Excess	Savings	
1	2	3	7	8	9	10	11	12	13	14	15	16	16	17	18	19	20
1	KSRRB300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	962.42	211.79	203831.44	1340.48	1203.03	211.79	254789.30	137.46	211.79	29111.59	1340.48	283900.89	80069.45	0.00	
2	KSRRB M2900-1. Plain cement concrete M10 mix with crushed stone aggregate 40mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing including cost of materials, labour, HOM complete as per the specification	Cum	143.99	4479.56	645011.84	196.90	179.99	4479.56	806264.81	16.91	4479.56	75760.56	196.90	882025.37	237013.53	0.00	
3	KSRRB M2200-6. Providing TMT Bars Fe 500 steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in postion, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification.	Ton	18.50	72326.98	1338049.13	24.34	23.13	72326.98	1672561.41	1.22	72326.98	88095.71	24.34	1760657.12	422607.99	0.00	
4	Providing and laying plain/reinforced cement concrete for side drains wall & bottom thickness 15cm using M20 nominal mix concrete with OPC at 300 kgs with 29mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregate at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specifications.	Cum	295.13	7070.20	2086610.45	395.28	368.91	7070.20	2608263.06	26.37	7070.20	186410.24	395.28	2794673.30	655670.21	0.00	
5	Supplying and fixing precast reinforced concrete slab 10cm thick of mix M20 using 20mm and downsize graded granite metal using reinforcement 10mm dia steel at 150mm C/c both ways cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges , labour charges inclusive of cost of cost of all materials (data Rate enclosed)	Sqm	603.45	2337.00	1410262.65	888.75	754.31	2337.00	1762828.31	134.44	2337.00	314180.44	888.75	2077008.75	666746.10	0.00	
6	Providing and laying Pre Cast Cover slabs of 250mm thick of mix M20 using graded granite jelly 20mm down size with steel reinforcement, including from work, lift charges, curing and concrete finished surfaces on both side etc. complete and as per drawing and direction of Engineer-in-charge of work (data Rate enclosed)	Sqm	39.96	5418.00	216503.28	39.96	39.96	5418.00	216503.28	0.00	5418.00	0.00	39.96	216503.28	0.00	0.00	
7	Providing and fixing pre cast solid concrete kerb stones of size 450x200x400 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete.	Nos	687.00	477.00	327699.00	1378.00	858.75	477.00	409623.75	519.25	477.00	247682.25	1378.00	657306.00	329607.00	0.00	
8	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	93.00	84.80	7886.40	186.09	116.25	84.80	9858.00	69.84	84.80	5922.43	186.09	15780.43	7894.03	0.00	
9	KSRRB M300-14. Excavation for Road Way in Hard rock by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications.	Cum	2099.63	43.46	91249.92	2074.69	2074.69	43.46	90166.11	0.00	43.46	0.00	2074.69	90166.11	0.00	1083.81	
10	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications.	Sqm	8398.50	6.36	53414.46	5186.73	5186.73	6.36	32987.60	0.00	6.36	0.00	5186.73	32987.60	0.00	20426.86	

	Description of Work	Unit	Qty as per ScheduleB			Total Qty Executed	Qty. as per Actuals upto 125%			Qty. as per Actuals above 125%			Total		Difference		Remarks
			Qty	Rates	Amount		Qty.	Rates	Amount	Qty.	Rates	Amount	Qty	Amount	Excess	Savings	
	2	3	7	8	9	10	11	12	13	14	15	16	10	17	18	19	20
	KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.	Cum	1931.66	2001.28	3865792.52	1192.95	1192.95	2001.28	2387422.77	0.00	2001.28	0.00	1192.95	2387422.77	0.00	1478369.75	
12	KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications.	Sqm	8398.50	33.92	284877.12	5186.73	5186.73	33.92	175933.88	0.00	33.92	0.00	5186.73	175933.88	0.00	108943.24	
13	KSRRB 500-2. Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM complete as per specifications.	Sqm	8398.50	5.30	44512.05	5186.73	5186.73	5.30	27489.67	0.00	5.30	0.00	5186.73	27489.67	0.00	17022.38	
14	KSRRB 500-7. Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications	Sqm	8398.50	12.72	106828.92	5186.73	5186.73	12.72	65975.21	0.00	12.72	0.00	5186.73	65975.21	0.00	40853.71	
15	KSRRB 500-11. Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by smooth wheeled, vibratory & tandem rollers to achieve the desired density, but excluding cost of primer / tack coat & including lead, lift and cost of all materials, labour, HOM complete as per specifications. 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 3.4% VG-30 Bitumen	Cum	419.93	7428.48	3119441.61	259.34	259.34	7428.48	1926476.00	0.00	7428.48	0.00	259.34	1926476.00	0.00	1192965.61	
16	Providing and laying bituminous concrete 40mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 507 of MORTH V revision as per IRC SP-53-2015. using 40-60 TPH capacity HMP with mechanical paver grading II (30-45mm) with 5.4 % of modified bituminus binder consisting of 4.97% of VG-30 bitumen (60/70 grade) and 0.43% of plastomeric thermoplastics (waste plastic)	Cum	335.94	8831.92	2966995.20	207.47	207.47	8831.92	1832351.38	0.00	8831.92	0.00	207.47	1832351.38	0.00	1134643.82	
17	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications.	Sqm	260.20	454.74	118323.35	156.74	156.74	454.74	71275.95	0.00	454.74	0.00	156.74	71275.95	0.00	47047.40	
					16939682.00				14350770.49			947163.22		15297933.71	2399608.31	4041356.58	
	EIRL																
11	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/trap/basalt material, mixing by mix in place method by rotavator at OMC,spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications.	Cum								778.01	1994.92	1552066.71	778.01	1552066.71	1552066.71		

Brunal Bengal

Description of Work	Unit	Qty as per Schedule8			Total Qty Executed	Qty. as per Actuals upto 125%			Qty. as per Actuals above 125%			Total		Difference		Remarks
		Qty	Rates	Amount		Qty.	Rates	Amount	Qty.	Rates	Amount	Qty	Amount	Excess	Savings	
2	3	7	8	9	10	11	12	13	14	15	16	10	17	18	19	20
E2 KSRRB M800-35. Supply and Installtion of Moulded Shank Raised Pavement Markers made of polycarbonate and ABS(Acrylonitrile Butadiene Styrene) moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering the lens face and shall support a load of 16000 kg tested in accordance to Specifications of Category A of MORTH Circular No RW/NH/33023/10-97 – DO III Dt.11.06. 1997. The height, width and length shall not exceed 50 mm, 100 mm and 102 mm and with minimum reflective area of 13 Sqcm on each side and the slope to the base shall be 35 degree. The strength of detachment of the integrated cylindrical shanks, (of diameter not less than 19 mm and height not less than 30 mm) from the body is to be a minimum value of 500 Kg. Fixing will be by drilling holes on the road for the shanks to go inside, without nails and using epoxy resin based adhesive as per manufacturer's recommendation and complete as directed by the engineer.	Nos								248.00	357.22	88590.56	248.00	88590.56	88590.56		
Sub Total													16938590.98	4040265.58	4041356.58	
Miscellaneous & Rounding off													1091.01	1091.01		
Total				16939682.00									16939681.99	4041356.59	4041356.58	

Assistant Engineer

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ಉಪವಿಭಾಗ,
ಬ.ಬ.ಎಂ.ಪಿ. ಬೆಂಗಳೂರು-106

Asst. Executive Engineer

Executive Engineer
B.B.M.P. Division
Yelahanka

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ಜಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ